Site Plans

Issued for: **Permitting**

Date Issued: December 13, 2013

Latest Issue: February 06, 2015

Sheet Index

Number	Drawing Title	Latest Issue
C-1	Legend and General Notes	12/19/2014
C-2	Overall Site Plan	12/19/2014
C-3	Stream Crossing Plan	2/6/2015
C-4	Overall Grading Plan EPSC Plan	2/6/2015
C-5	Stormwater Treatment Pond 1 Plan	2/6/2015
C-6	Stormwater Treatment Pond 2 Plan	12/13/2013
C-7	Site Section A-A: Extraction Limits	12/13/2013
C-8	Details	12/13/2013
C-9	Details	12/13/2013
C-10	Details	1/27/2014
C-11	Details	1/27/2014
RP-1	Reclamation Plan	12/19/2014

Halifax Quarry

Halifax, VT



Site Location Map

Property Owners

Owner/Applicant
C.A. Denison Lumber Co., Inc.
5076 Stage Road
Halifax, VT 05358
Phone · Fax

Vanasse Hangen Brustlin, Inc.
Transportation
Land Development
Environmental Services

7056 U.S. Route 7, P.O. Box 120
North Ferrisburgh, Vermont 05473
802.497.6100 • FAX 802.425.7799

VHB Project No. 57595.00
Halifax, VT
Issued for: Permitting

Legend

Exist.	Prop.	
10+00	10+00	PROJECT DEMARCATION FENCE
		BASELINE
		WETLAND LINE WITH FLAG
BZ		WETLAND BUFFER ZONE
		GRAVEL ROAD
		STREAM / POND / WATER COURSE
		DETENTION BASIN
X	X	SILT FENCE
		SILT SOCK / STRAW WATTLE
12"D	12"D	DRAIN
4	4	MINOR CONTOUR
20	20	MAJOR CONTOUR
132.75 ×	132.75 ×	SPOT ELEVATION
		RIPRAP / STONE FILL
		NATURAL SUBSTRATE MATERIAL MIX

Abbreviations

General

APPROX	APPROXIMATE
BS	BOTTOM OF SLOPE
EL	ELEVATION
ELEV	ELEVATION
EXIST	EXISTING
LOD	LIMIT OF DISTURBANCE
MAX	MAXIMUM
MIN	MINIMUM
NTS	NOT TO SCALE
PROP	PROPOSED
TS	TOP OF SLOPE
TYP	TYPICAL

Utility

CMP	CORRUGATED METAL PIPE
FES	FLARED END SECTION
HDPE	HIGH DENSITY POLYETHYLENE PIPE
INV	INVERT ELEVATION
I=	INVERT ELEVATION
PVC	POLYVINYLCHLORIDE PIPE
RCP	REINFORCED CONCRETE PIPE
R=	RIM ELEVATION

Notes

General

1. CONTRACTOR SHALL NOTIFY "DIG-SAFE" (1-888-344-7233) AT LEAST 72 HOURS BEFORE EXCAVATING.
2. CONTRACTOR SHALL BE RESPONSIBLE FOR SITE SECURITY AND JOB SAFETY. CONSTRUCTION ACTIVITIES SHALL BE IN ACCORDANCE WITH OSHA STANDARDS AND LOCAL REQUIREMENTS.
3. DISTURBANCE OUTSIDE THE LIMITS OF PROPOSED WORK IS NOT ALLOWED AND IS A VIOLATION OF THIS PERMIT.
4. IN THE EVENT THAT SUSPECTED CONTAMINATED SOIL, GROUNDWATER, AND OTHER MEDIA ARE ENCOUNTERED DURING EXCAVATION AND CONSTRUCTION ACTIVITIES BASED ON VISUAL, OLFACTORY, OR OTHER EVIDENCE, THE CONTRACTOR SHALL STOP WORK IN THE VICINITY OF THE SUSPECT MATERIAL TO AVOID FURTHER SPREADING OF THE MATERIAL, AND SHALL NOTIFY THE OWNER IMMEDIATELY SO THAT THE APPROPRIATE TESTING AND SUBSEQUENT ACTION CAN BE TAKEN.
5. CONTRACTOR SHALL PREVENT DUST, SEDIMENT, AND DEBRIS FROM EXITING THE SITE AND SHALL BE RESPONSIBLE FOR CLEANUP, REPAIRS AND CORRECTIVE ACTION IF SUCH OCCURS.
6. DAMAGE RESULTING FROM CONSTRUCTION LOADS SHALL BE REPAIRED BY THE CONTRACTOR AT NO ADDITIONAL COST TO OWNER.
7. CONTRACTOR SHALL CONTROL STORMWATER RUNOFF DURING CONSTRUCTION TO PREVENT ADVERSE IMPACTS TO OFF SITE AREAS, AND SHALL BE RESPONSIBLE TO REPAIR RESULTING DAMAGES, IF ANY, AT NO COST TO OWNER.
8. THIS PROJECT DISTURBS MORE THAN ONE ACRE OF LAND AND FALLS WITHIN THE NPDES CONSTRUCTION GENERAL PERMIT (CGP) PROGRAM AND EPA JURISDICTION. A VERMONT STATE CONSTRUCTION-PHASE STORMWATER PERMIT IS REQUIRED FOR THIS PROJECT. REFER TO THE PLANS, PERMIT APPLICATION, AND PENDING PERMIT AUTHORIZATION FOR MORE DETAILS OUTLINING CONSTRUCTION REQUIREMENTS.
9. DESIGNS AND PROPOSED SITE INFORMATION IS BASED OFF OF AERIAL SURVEY PROVIDED BY OTHERS. PRIOR TO CONSTRUCTION, THE CONTRACTOR IS TO VERIFY AND REPORT TO ENGINEER THE EXISTING ELEVATIONS AND LOCATIONS OF ALL PROPOSED ITEMS, INCLUDING CULVERTS, ROADWAY, AND STORMWATER TREATMENT FACILITIES.
10. ALL STAGING AND STOCKPILING OF EQUIPMENT AND MATERIALS SHALL OCCUR WITHIN PROJECT BOUNDARIES.

Utilities

1. THE LOCATIONS, SIZES, AND TYPES OF EXISTING UTILITIES ARE SHOWN AS AN APPROXIMATE REPRESENTATION ONLY. THE OWNER OR IT'S REPRESENTATIVE(S) HAVE NOT INDEPENDENTLY VERIFIED THIS INFORMATION AS SHOWN ON THE PLANS. THE UTILITY INFORMATION SHOWN DOES NOT GUARANTEE THE ACTUAL EXISTENCE, SERVICEABILITY, OR OTHER DATA CONCERNING THE UTILITIES, NOR DOES IT GUARANTEE AGAINST THE POSSIBILITY THAT ADDITIONAL UTILITIES MAY BE PRESENT THAT ARE NOT SHOWN ON THE PLANS. PRIOR TO ORDERING MATERIALS AND BEGINNING CONSTRUCTION, THE CONTRACTOR SHALL VERIFY AND DETERMINE THE EXACT LOCATIONS, SIZES, AND ELEVATIONS OF THE POINTS OF CONNECTIONS TO EXISTING UTILITIES AND, SHALL CONFIRM THAT THERE ARE NO INTERFERENCES WITH EXISTING UTILITIES AND THE PROPOSED UTILITY ROUTES, INCLUDING ROUTES WITHIN THE PUBLIC RIGHTS OF WAY.
2. WHERE AN EXISTING UTILITY IS FOUND TO CONFLICT WITH THE PROPOSED WORK, OR EXISTING CONDITIONS DIFFER FROM THOSE SHOWN SUCH THAT THE WORK CANNOT BE COMPLETED AS INTENDED, THE LOCATION, ELEVATION, AND SIZE OF THE UTILITY SHALL BE ACCURATELY DETERMINED WITHOUT DELAY BY THE CONTRACTOR, AND THE INFORMATION FURNISHED IN WRITING TO THE OWNER'S REPRESENTATIVE FOR THE RESOLUTION OF THE CONFLICT AND CONTRACTOR'S FAILURE TO NOTIFY PRIOR TO PERFORMING ADDITIONAL WORK RELEASES OWNER FROM OBLIGATIONS FOR ADDITIONAL PAYMENTS WHICH OTHERWISE MAY BE WARRANTED TO RESOLVE THE CONFLICT.
3. SET INVERTS OF DRAINS AND DITCHES IN ACCORDANCE WITH ELEVATIONS SHOWN ON THE PLANS.
4. UTILITY PIPE MATERIALS SHALL BE AS FOLLOWS, UNLESS OTHERWISE NOTED ON THE PLAN:
   A. STORM DRAINAGE PIPES SHALL BE SMOOTH INTERIOR, CORRUGATED-EXTERIOR HDPE (ADS N-12 OR EQUAL)
   B. PIPE INSTALLATION AND MATERIALS SHALL COMPLY WITH MANUFACTURER'S INSTALLATION RECOMMENDATIONS.
5. ALL DRAINAGE AND SANITARY STRUCTURE INTERIOR DIAMETERS (4' MIN.) SHALL BE DETERMINED BY THE MANUFACTURER BASED ON THE PIPE CONFIGURATIONS SHOWN ON THESE PLANS.

Layout and Materials

1. DIMENSIONS ARE FROM THE TOP OF SLOPE, BOTTOM OF SLOPE, CENTER OF ROAD, OR AS INDICATED ON THE PLANS.
2. PROPOSED BOUNDS AND ANY EXISTING PROPERTY LINE MONUMENTATION DISTURBED DURING CONSTRUCTION SHALL BE SET OR RESET BY A PROFESSIONAL LICENSED SURVEYOR.
3. PRIOR TO START OF CONSTRUCTION, CONTRACTOR SHALL VERIFY EXISTING GROUND ELEVATIONS AND STREAM LOCATIONS ADJACENT TO DRAINAGE OUTLETS TO ASSURE PROPER TRANSITIONS BETWEEN EXISTING AND PROPOSED GRADES.
4. SYMBOLS AND LEGENDS OF PROJECT FEATURES ARE GRAPHIC REPRESENTATIONS AND ARE NOT NECESSARILY SCALED TO THEIR ACTUAL DIMENSIONS OR LOCATIONS ON THE DRAWINGS. THE CONTRACTOR SHALL REFER TO THE DETAIL SHEET DIMENSIONS, MANUFACTURERS' LITERATURE, SHOP DRAWINGS AND FIELD MEASUREMENTS OF SUPPLIED PRODUCTS FOR LAYOUT OF THE PROJECT FEATURES.
5. CONTRACTOR SHALL NOT RELY SOLELY ON ELECTRONIC VERSIONS OF PLANS, SPECIFICATIONS, AND DATA FILES THAT ARE OBTAINED FROM THE DESIGNERS, BUT SHALL VERIFY LOCATION OF PROJECT FEATURES IN ACCORDANCE WITH THE PAPER COPIES OF THE PLANS AND SPECIFICATIONS THAT ARE SUPPLIED AS PART OF THE CONTRACT DOCUMENTS.

Demolition

1. CONTRACTOR SHALL DISPOSE OF DEMOLITION DEBRIS IN ACCORDANCE WITH APPLICABLE FEDERAL, STATE AND LOCAL REGULATIONS, ORDINANCES AND STATUTES.
2. UNLESS OTHERWISE SPECIFICALLY PROVIDED ON THE PLANS OR IN THE SPECIFICATIONS, THE ENGINEER HAS NOT PREPARED DESIGNS FOR AND SHALL HAVE NO RESPONSIBILITY FOR THE PRESENCE, DISCOVERY, REMOVAL, ABATEMENT OR DISPOSAL OF HAZARDOUS MATERIALS, TOXIC WASTES OR POLLUTANTS AT THE PROJECT SITE. THE ENGINEER SHALL NOT BE RESPONSIBLE FOR ANY CLAIMS OF LOSS, DAMAGE, EXPENSE, DELAY, INJURY OR DEATH ARISING FROM THE PRESENCE OF HAZARDOUS MATERIAL AND CONTRACTOR SHALL INDEMNIFY AND HOLD HARMLESS THE ENGINEER FROM ANY CLAIMS MADE IN CONNECTION THEREWITH. MOREOVER, THE ENGINEER SHALL HAVE NO ADMINISTRATIVE OBLIGATIONS OF ANY TYPE WITH REGARD TO ANY CONTRACTOR AMENDMENT INVOLVING THE ISSUES OF PRESENCE, DISCOVERY, REMOVAL, ABATEMENT OR DISPOSAL OF ASBESTOS OR OTHER HAZARDOUS MATERIALS.

Existing Conditions Information

1. BASE PLAN: THE TOPOGRAPHY AND PHYSICAL FEATURES ARE BASED ON AN AERIAL SURVEY PERFORMED BY EASTERN TOPOGRAPHICS IN MAY, 2009. ADDITIONAL GROUND CONTROL SURVEY WAS CONDUCTED BY EASTERN TOPOGRAPHICS IN MAY, 2009. PROPERTY BOUNDARY INFORMATION WAS PROVIDED BY DENISON LUMBER CO., INC., AND DOES NOT LIE WITHIN PROJECT LIMITS. NO BOUNDARY RESEARCH, DETERMINATION, OR LOCATIONS WAS PROVIDED BY VHB.
   A. DELINEATION OF THE WETLANDS AND PLACEMENT OF THE FLAGS WAS PERFORMED BY: VHB IN 2012 AND 2013.
   B. FLAGS MARKING THE WETLANDS WERE LOCATED BY: VHB VIA GPS IN 2012 AND 2013.
2. TOPOGRAPHY:
   A. HORIZONTAL DATUM IS VERMONT STATE PLANE NAD83/2011.
   B. ELEVATIONS ARE BASED ON NAVD88.

Document Use

1. THESE PLANS AND CORRESPONDING CADD DOCUMENTS ARE INSTRUMENTS OF PROFESSIONAL SERVICE, AND SHALL NOT BE USED, IN WHOLE OR IN PART, FOR ANY PURPOSE OTHER THAN FOR WHICH IT WAS CREATED WITHOUT THE EXPRESSED, WRITTEN CONSENT OF VHB. ANY UNAUTHORIZED USE, REUSE, MODIFICATION OR ALTERATION, INCLUDING AUTOMATED CONVERSION OF THIS DOCUMENT SHALL BE AT THE USER'S SOLE RISK WITHOUT LIABILITY OR LEGAL EXPOSURE TO VHB.

General EPSC Notes:

1. TEMPORARY EPSC MEASURES INTENDED TO TRAP SEDIMENT SHALL BE INSTALLED AS A FIRST STEP IN LAND DISTURBING ACTIVITIES AND SHALL BE MADE FUNCTIONAL BEFORE UPSLOPE LAND DISTURBANCE TAKES PLACE, WITH THE EXCEPTION OF THOSE LAND DISTURBING ACTIVITIES THAT ARE NECESSARY TO INSTALL MEASURES.
2. EPSC MEASURES SHALL BE INSTALLED PURSUANT TO THE CONSTRUCTION PHASE STORMWATER DISCHARGE PERMIT FOR THE PROJECT, THIS EPSC PLAN, THE VERMONT STANDARDS AND SPECIFICATIONS FOR EROSION PREVENTION AND SEDIMENT CONTROL (2006), VERMONT EROSION PREVENTION AND SEDIMENT CONTROL FIELD GUIDE (2006), AND ANY OTHER RELEVANT PROJECT PERMITS AND RESOURCES.
3. PROPOSED MINOR CHANGES TO THE EPSC PLAN SHALL BE APPROVED BY THE ON-SITE PLAN COORDINATOR (OSPC) OR HIS/HER DESIGNEE PRIOR TO IMPLEMENTATION.
4. LOGGING ACTIVITIES SHALL BE CONDUCTED IN ACCORDANCE WITH ACCEPTABLE MANAGEMENT PRACTICES FOR MAINTAINING WATER QUALITY ON LOGGING JOBS IN VERMONT (AMPS, 2006).
5. ALL PARTIES ASSOCIATED WITH CONSTRUCTION ACTIVITIES WHO MEET EITHER OF THE FOLLOWING TWO CRITERIA OF "PRINCIPAL OPERATOR" MUST OBTAIN COVERAGE UNDER THE CONSTRUCTION STORMWATER DISCHARGE PERMIT FOR THE PROJECT PRIOR TO COMMENCEMENT OF CONSTRUCTION ACTIVITIES BY THAT OPERATOR:
   a. THE PARTY HAS OPERATIONAL CONTROL OVER CONSTRUCTION PLANS AND SPECIFICATIONS, INCLUDING BUT NOT LIMITED TO THE ABILITY TO MAKE MODIFICATIONS TO THOSE PLANS AND SPECIFICATIONS; OR
   b. THE PARTY HAS CONTINUOUS DAY-TO-DAY OPERATIONAL CONTROL OF THOSE ACTIVITIES AT THE PROJECT THAT ARE NECESSARY TO ENSURE COMPLIANCE WITH THE EPSC PLAN FOR THE SITE OR OTHER PERMIT CONDITIONS (E.G., THEY ARE AUTHORIZED TO DIRECT WORKERS AT A SITE TO CARRY OUT ACTIVITIES REQUIRED BY THE EPSC PLAN OR COMPLY WITH OTHER PERMIT CONDITIONS).

Construction EPSC Notes:

1. EXISTING VEGETATION SHALL BE PROTECTED AND MAINTAINED TO THE EXTENT PRACTICABLE.
2. A VEGETATED BUFFER SHALL BE MAINTAINED FOR WATER BODIES (E.G., WETLANDS, STREAMS, AND WETLAND AND STREAM BUFFERS), WHERE FEASIBLE AND AS SPECIFIED IN ANY RELEVANT WETLAND PERMITS OR STREAM ALTERATION PERMITS.
3. AREAS CLEARED OF VEGETATION FOR STORMWATER BASINS MAY BE USED FOR TEMPORARY SEDIMENT TRAPS AND TEMPORARY SEDIMENT BASINS, AS NEEDED; TO BE RECONSTRUCTED AS OPERATIONAL STORMWATER TREATMENT PRACTICES FOLLOWING CONSTRUCTION PER THE PERMITTED OPERATIONAL PHASE STORMWATER MANAGEMENT PLAN.
4. TO THE EXTENT PRACTICABLE, SURFACE FLOW SHALL BE DIVERTED AWAY FROM EXPOSED SOILS.
5. RESOURCE AREAS (E.G., WETLANDS, STREAMS, AND WETLANDS AND STREAM BUFFERS) SHALL BE FLAGGED PRIOR TO ANY CONSTRUCTION RELATED ACTIVITIES OCCURRING WITHIN CLOSE PROXIMITY TO THOSE AREAS
6. EFFLUENT FROM DEWATERING OPERATIONS SHALL BE FILTERED OR PASSED THROUGH A SEDIMENT TRAPPING DEVICE AND DISCHARGED IN A MANNER THAT DOES NOT RESULT IN IMPACTS TO WATER QUALITY OR CONTRIBUTE TO EROSION.
7. UNDERGROUND UTILITY LINES SHALL BE INSTALLED IN ACCORDANCE WITH THE FOLLOWING STANDARDS IN ADDITION TO THE OTHER APPLICABLE CRITERIA:
   a. NO MORE THAN 500 LINEAR FEET OF TRENCH MAY BE OPENED AT ONE TIME.
   b. EXCAVATED MATERIAL SHALL BE PLACED IN UPLAND AREAS ON THE UPHILL SIDE OF THE TRENCHES, WHERE FEASIBLE.
8. SEDIMENT REMOVED FROM SEDIMENT CONTROL PRACTICES SHALL BE DISPOSED OF IN AN UPLAND AREA OUTSIDE OF THE 50' WETLAND BUFFER WITH STABILIZATION FOLLOWING DISPOSAL OF MATERIAL.
9. IN ADVANCE OF FORECASTED RAINFALL OR SNOWMELT, EPSC MEASURES THAT ARE LOCATED IN AREAS OF ACTIVE EARTH DISTURBANCE SHALL BE INSPECTED AND REPAIRED, AS NEEDED.
10. STABILIZED CONSTRUCTION ENTRANCES SHALL BE REGULARLY MAINTAINED TO CONTROL EQUIPMENT AND VEHICLES FROM TRACKING MATERIAL OFF SITE.
10. DUST CONTROL SHALL BE HANDLED VIA WATER OR CALCIUM CHLORIDE APPLICATION TO ROADWAYS AND OTHER AREAS WHERE DUST MAY BE GENERATED.
11. STEEP SIDE SLOPES SHALL BE STABILIZED WITH STONE OR SEED/ROLLED EROSION CONTROL PRODUCT..
12. CONSTRUCTION DEMARCATION AND PERIMETER CONTROLS LOCATED WITHIN 50 FT OF WATERS OF THE STATE (WOS) SHALL COMPLY WITH CONSTRUCTION DEMARCATION AND PERIMETER CONTROL NOTES ON THIS SHEET.

Winter Construction Notes:

1. WINTER CONSTRUCTION SEASON IS DEFINED BY VT DEC AS OCTOBER 15 TO APRIL 15.
2. THE FOLLOWING WINTER CONSTRUCTION CONDITIONS APPLY TO THOSE CONSTRUCTION ACTIVITIES INVOLVING EARTH DISTURBANCE BETWEEN OCTOBER 15 AND APRIL 15:
   a. FOR AREAS STABILIZED BY VEGETATION, SEED SHALL BE APPLIED NO LATER THAN SEPTEMBER 15.
   b. MULCH SHALL BE APPLIED AT DOUBLE THE REGULAR CONSTRUCTION SEASON RATE OR ROUGHLY 2 INCHES OF MULCH WITH 80 TO 90% COVER (SEE "MULCH" DETAIL). MULCH SHALL BE TRACKED IN OR STABILIZED WITH NETTING.
   c. ENLARGE ACCESS POINTS AS NEEDED TO PROVIDE SPACE FOR SNOW STOCKPILING..
   d. CLEARED SNOW SHALL BE PLACED DOWN GRADIENT OF ALL AREAS OF DISTURBANCE WHERE FEASIBLE.
   e. SNOW SHALL NOT BE PLACED IN STORMWATER TREATMENT STRUCTURES. (E.G. BASINS)
   f. TO THE EXTENT PRACTICABLE, A MINIMUM 25-FOOT BUFFER FROM PERIMETER CONTROLS (E.G., SILT FENCE) SHALL BE MAINTAINED TO ALLOW FOR SNOW CLEARING AND MAINTENANCE.
   g. FOR AREAS OF DISTURBANCE WITHIN 50 FEET OF A RECEIVING WATER, SILT FENCE SHALL BE REINFORCED OR ELSE REPLACED WITH PERIMETER DIKES, SWALES, OR OTHER PRACTICES RESISTANT TO THE FORCES OF SNOW LOADS, AS NEEDED.
   h. DRAINAGE STRUCTURES ARE TO BE KEPT OPEN AND FREE OF SNOW AND ICE DAMS WHERE FEASIBLE AS DETERMINED BY THE OSPC.
   i. SNOW AND ICE SHALL BE REMOVED TO LESS THAN 1 INCH THICKNESS PRIOR TO STABILIZATION, TO EXTENT FEASIBLE.
   j. A 10 TO 20-FOOT WIDE STONE PAD SHALL BE USED IN AREAS WHERE CONSTRUCTION VEHICLE TRAFFIC IS ANTICIPATED (E.G., AROUND THE PERIMETER OF A BUILDING, WHERE APPLICABLE.
   k. TO ENSURE COVER OF DISTURBED SOIL IN ADVANCE OF A SNOWMELT EVENT, AREAS OF DISTURBED SOIL SHALL BE STABILIZED AT THE END OF EACH WORKDAY, UNLESS
      i. WORK IS TO CONTINUE WITHIN THE AREA WITHIN THE NEXT 24 HOURS AND THERE IS NO PRECIPITATION FORECAST OF THE NEXT 24 HOURS OR
      ii. WORK IS OCCURRING IN A SELF-CONTAINED EXCAVATION (I.E., NO OUTLET) WITH A DEPTH OF 2 FEET OR GREATER (E.G., UTILITY TRENCHES).

Temporary and Final Stabilization Notes:

1. DURING REGULAR CONSTRUCTION SEASON, ALL AREAS OF EARTH DISTURBANCE MUST BE STABILIZED WITHIN 14 DAYS OF INITIAL DISTURBANCE. AFTER THIS INITIAL 14-DAY PERIOD, ALL EARTH DISTURBANCE AREAS MUST BE STABILIZED ON A DAILY BASIS, WITH THE FOLLOWING EXCEPTIONS:
   ii. STABILIZATION IS NOT REQUIRED IF WORK IS TO CONTINUE WITHIN THE AREA WITHIN THE NEXT 24 HOURS AND THERE IS NO PRECIPITATION FORECAST FOR THE NEXT 24 HOURS.
   ij. STABILIZATION IS NOT REQUIRED IF THE WORK IS OCCURRING IN A SELF-CONTAINED EXCAVATION (I.E., NO OUTLET FOR STORMWATER) WITH A DEPTH OF 2 FEET OR GREATER (E.G., UNDERGROUND LINE INSTALLATION).
2. DURING "WINTER CONSTRUCTION," (OCTOBER 15 TO APRIL 15) DISTURBED SOIL MUST BE STABILIZED AT THE END OF EACH DAY, WITH THE FOLLOWING EXCEPTIONS:
   a. IF NO PRECIPITATION WITHIN 24 HOURS IS FORECAST AND WORK WILL RESUME IN THE SAME DISTURBED AREA WITHIN 24 HOURS, DAILY STABILIZATION IS NOT NECESSARY.
   b. STABILIZATION IS NOT REQUIRED IF THE WORK IS OCCURRING IN A SELF-CONTAINED EXCAVATION (I.E., NO OUTLET FOR STORMWATER) WITH A DEPTH OF 2 FEET OR GREATER (E.G., UNDERGROUND LINE INSTALLATION).
3. DISTURBANCE ACTIVITIES MUST BE COORDINATED TO ENSURE THAT THE ALLOWABLE CONCURRENT EARTH DISTURBANCE OF 2 ACRES IS NOT EXCEEDED.
4. TEMPORARY SOIL STABILIZATION SHALL BE ACHIEVED BY MULCH, SEED AND MULCH, STONE, AND/OR ROLLED EROSION CONTROL PRODUCTS (E.G., EROSION CONTROL BLANKET). MULCH SHALL BE COMPRISED OF STRAW.
5. PERMANENT STABILIZATION SHALL BE ACHIEVED BY 70% VEGETATION COVER, STONE, ASPHALT, BEDROCK, OR OTHER PERMANENT MATERIAL THAT PROVIDES COMPLETE COVER OF EXPOSED SOILS.
6. AREAS THAT HAVE REACHED TEMPORARY OR FINAL STABILIZATION SHALL NOT BE CONSIDERED PART OF TOTAL AREA OF EARTH DISTURBANCE.
7. AN APPROPRIATE WETLAND SEED MIX SHALL BE APPLIED TO ANY TEMPORARILY DISTURBED WETLAND AREAS. AN UPLAND CONSERVATION MIX SHALL BE APPLIED TO ANY TEMPORARILY DISTURBED UPLAND AREAS. FOR AN AREA TO BE STABILIZED FOR WINTER BY VEGETATED COVER, SEEDING MUST BE COMPLETED BY SEPTEMBER 15, WEATHER DEPENDENT.
8. AREAS TO BE STABILIZED FOR WINTER THAT DO NOT HAVE ESTABLISHED VEGETATION BY OCTOBER 15 SHALL BE STABILIZED BY ANCHORED MULCH AT THE WINTER APPLICATION RATE, OR OTHER APPROVED STABILIZATION MEASURES (E.G., ROLLED EROSION CONTROL PRODUCT). DORMANT SEEDING WITH AN APPROPRIATE WETLAND SEED MIX IN TEMPORARILY DISTURBED WETLAND AREAS OR AN APPROPRIATE UPLAND CONSERVATION MIX IN TEMPORARILY DISTURBED UPLAND AREAS IS RECOMMENDED.
9. ALL TEMPORARY EPSC MEASURES SHALL BE REMOVED WITHIN 30 DAYS AFTER FINAL SITE STABILIZATION OR AFTER THE TEMPORARY EPSC MEASURES ARE NO LONGER NEEDED.

General Construction Sequence Notes:

1. THE SEQUENCE OF SITE CONSTRUCTION IS GENERALLY EXPECTED TO OCCUR AS FOLLOW:
   a. INSTALL CONSTRUCTION DEMARCATION TO DEFINE MAX LIMITS OF DISTURBANCE
   b. INSTALL SILT FENCE AND OTHER EROSION CONTROL MEASURES WHERE SHOWN ON PLANS IN AREAS WHERE WORK IS ABOUT TO OCCUR
   c. INSTALL STREAM CROSSING CULVERTS/STRUCTURES.
   d. EXCAVATE AND CONSTRUCT STORMWATER TREATMENT PONDS, FOREBAYS, AND OUTLETS. NEW TREATMENT PONDS ARE TO RECEIVE FLOWS FROM NEW IMPERVIOUS AREAS DURING CONSTRUCTION. MAINTENANCE OF NEW FOREBAYS (SEDIMENT REMOVAL) MAY BE REQUIRED DURING CONSTRUCTION TO MAINTAIN PROPER TREATMENT SYSTEM FUNCTION.
   e. ACCESS ROAD AND SWALE CONSTRUCTION, WITH SWALES DIRECTING NEW RUNOFF TO STORMWATER TREATMENT PONDS AS SHOWN ON THE PLANS.
   f. INSTALLATION OF ADDITIONAL, NON-STREAM CROSSING CULVERTS TO OCCUR DURING ROAD CONSTRUCTION.
   g. EXTRACTION OPERATION BEGINS, WITH TREE AND VEGETATION REMOVAL WITHIN THE EXTRACTION-AREA OCCURRING AS NECESSARY.
   h. NOTE: STABILIZATION MEASURES ARE TO OCCUR CONTINUOUSLY AS CONSTRUCTION PROGRESSES, PER THE CONDITIONS OF THE STORMWATER PERMITS.

CONSTRUCTION DEMARCATION:

1. CONSTRUCTION DEMARCATION TO BE INSTALLED ALONG PERIMETER OF LIMITS OF DISTURBANCE PER THE EPSC PLAN.
2. DEMARCATION IS NOT TO CROSS ACTIVE ACCESS ROUTES.
3. WITHIN 50 FEET OF MAPPED WATER RESOURCE AREAS, DEMARCATION MUST INCLUDE:
   a. 2 TO 3 ROWS OF STAKED (OR STAPLED) 6 INCH ORANGE BARRIER MESH TAPE,
   b. ORANGE CONSTRUCTION FENCE, OR
   c. ORANGE SNOW FENCE.
4. GREATER THAN 50 FEET FROM MAPPED WATER RESOURCE AREAS, DEMARCATION MAY INCLUDE:
   a. ONE ROW OF STAKED (OR STAPLED) 6 INCH ORANGE BARRIER MESH TAPE, OR
   b. ORANGE FLAGGING.

PERIMETER CONTROLS:

1. PERIMETER CONTROLS ARE TO BE INSTALLED ON DOWNSLOPE SIDE OF AREAS OF DISTURBANCE WHERE THERE IS POTENTIAL FOR SEDIMENT RUNOFF AND/OR SOIL EROSION.
2. PERIMETER CONTROLS ARE NOT TO CROSS ACTIVE ACCESS ROUTES OR PERENNIAL FLOW PATHS (E.G., A STREAM).
3. PARTICULAR CARE IS TO BE TAKEN WHEN INSTALLING PERIMETER CONTROLS IN A WETLAND.
4. WITHIN 50 FEET OF MAPPED WATER RESOURCE AREAS, PERIMETER CONTROLS MUST INCLUDE:
   a. REINFORCED SILT FENCE – TO BE REINFORCED WITH WIRE MESH, STAKED HAYBALES, STAKED FIBER ROLLS, OR EROSION CONTROL MIX BERMS.
   b. STONE BERMS OR OTHER INTERCHANGEABLE AND/OR DEC APPROVED MEASURES.
5. GREATER THAN 50 FEET FROM MAPPED WATER RESOURCE AREAS, PERIMETER CONTROLS MAY INCLUDE:
   a. SILT FENCE (NON-REINFORCED)
   b. STAKED FIBER ROLLS, OR
   c. EROSION CONTROL MIX BERMS.

VHB

Vanasse Hangen Brustlin, Inc.

Transportation
Land Development
Environmental Services

7056 U.S. Route 7, P.O. Box 120
North Ferrisburgh, Vermont 05473
802.497.6100 • FAX 802.425.7799

No.	Revision	Date	Appvd.
2	ANR comments	12/19/14	TM
1	Revision per DEC comments	1/27/14	TM

Designed by | Drawn by | Checked by

CAD checked by | Approved by

Scale N/A | Date December 13, 2013

Project Title

Halifax Quarry
C.A. Denison Lumber Co., Inc.
Halifax, Vermont

Issued for

Permitting

Not Approved for Construction

Drawing Title

Legend and General Notes

Drawing Number

C-1

Sheet 1 of 11

Project Number 57595.00



ALIGNMENT CURVE DATA			
CURVE	PC	PT	PI
BEGIN ROAD	N 104836.47 E 1587850.80	N 104841.69 E 1587846.16	N 104912.7877 E 1587782.9775
C1	N 104841.69 E 1587846.16	N 104908.65 E 1587687.96	N 104912.7877 E 1587782.9775
C2	N 104894.28 E 1587358.46	N 104894.15 E 1587345.04	N 104893.9901 E 1587351.7515
C3	N 104902.51 E 1586990.73	N 105001.51 E 1586822.79	N 104905.1382 E 1586879.1276
C4	N 105450.52 E 1586560.28	N 105398.05 E 1586229.03	N 105848.8578 E 1586327.4029
C5	N 105288.12 E 1586205.04	N 105108.33 E 1586218.63	N 105196.1961 E 1586184.9827
END ROAD	N 105108.33 E 1586218.63	N 104892.57 E 1586301.24	N 104892.5676 E 1586301.2399

VHB
Vanasse Hangen Brustlin, Inc.
Transportation
Land Development
Environmental Services
7056 U.S. Route 7, P.O. Box 120
North Ferrisburgh, Vermont 05473
802.497.6100 • FAX 802.425.7799

80 0 80 160
SCALE IN FEET

No.	Revision	Date	Appvd.
1	ANR Comments	12/19/2014	TMG

Designed by | Drawn by | Checked by
CAD checked by | Approved by
Scale 1" = 80' | Date December 13, 2013

Project Title
Halifax Quarry
C.A.Denison Lumber Co., Inc.

Halifax, Vermont

Issued for
Permitting

Not Approved for Construction

Drawing Title
Overall Site Plan
Existing Conditions

Drawing Number
C-2

Sheet 2 of 11

Project Number
57595.00



SITE PLAN
SCALE: 1" = 10'

NOTES:
1. LOCATION OF CULVERT SHOWN ON PLANS IS BASED ON AERIAL SURVEY PROVIDED AND VHB DELINEATED STREAM LOCATION. VERIFY DEPICTED LOCATION OF CULVERT IN FIELD; REPORT CONDITIONS FOUND AND ANY APPARENT DISCREPANCIES TO ENGINEER PRIOR TO CONDUCTING WORK. ACTUAL PLACEMENT OF CULVERT AND DETERMINATION OF INVERT ELEVATIONS AND CULVERT SLOPE TO BE DONE IN FIELD WITH ENGINEER INPUT TO REFLECT TRUE STREAM CONDITIONS.
2. ALL IN-STREAM WORK IS TO OCCUR DURING FLOW BYPASS ACTIVITIES (IE. BYPASS PIPING OR PUMPING). NO IN-STREAM WORK IS PERMITTED WHILE WATER IS FLOWING THROUGH THE WORK ZONE.
3. STREAMBED STONE FILL TYPE E2 (PER THE VERMONT STANDARD RIVER MANAGEMENT PRINCIPLES AND PRACTICES (SRMPP) MANUAL, APPENDIX M) SHALL BE APPLIED IN ALL IN-STREAM AREAS OF RESTORATION, INCLUDING WITHIN THE CULVERT INVERT. TYPE E2 STONE FILL IS A GRADED STONE-PARTICLE MIX MEETING THE FOLLOWING CRITERIA:
   – THE LONGEST STONE DIMENSION IS 24" MIN
   – 50% OF THE TOTAL VOLUME OF STONE FILL SHALL HAVE A LEAST DIMENSION OF 18 INCHES (d50 = 18")
   – 25–35% OF THE STONE FILL VOLUME SHALL HAVE A MAXIMUM DIMENSION OF 2 INCHES, AND BE WELL-GRADED MATERIAL
4. STONE FILL MATERIAL SHALL BE PLACED IN 1.5 FOOT LIFTS AND THE MATERIAL HYDRAULICALLY FLUSHED BETWEEN LIFTS TO ENSURE THAT FINER PARTICLES ARE WASHED INTO THE VOIDS SURROUNDING LARGER ROCKS. THE INTENT IS TO CREATE A STREAM CHANNEL OF NATURAL APPEARANCE AND FUNCTION. ADEQUATE GRANULAR FINES ARE REQUIRED IN THE MIX TO PREVENT SUBSURFACE STREAM FLOW.
5. DISTURBED PORTIONS OF CHANNEL AT EACH END OF THE CULVERT SHALL BE STABILIZED WITH A MINIMUM THICKNESS OF 1.5 FEET OF STREAMBED STONE FILL TYPE E2. THIS MATERIAL SHALL BE PLACED AS NECESSARY TO DISSIPATE ENERGY AND TO PROVIDE AN ADEQUATE TRANSITION BETWEEN THE EMBEDDED CULVERT MATERIALS AND THE NATURAL CHANNEL SUBSTRATE.
6. GRANULAR BACKFILL FOR STRUCTURES SHALL BE A WELL GRADED FREE DRAINING GRANULAR MATERIAL, REASONABLY FREE FROM LOAM, SILT, CLAY, AND ORGANIC MATERIAL, AND MEET THE FOLLOWING GRADATION REQUIREMENTS:
   100% PASSING THE 3" SIEVE
   45–75% PASSING THE NO. 4 SIEVE
   0–12% PASSING THE NO. 100 SIEVE
   0–6% PASSING THE NO. 200. SIEVE
7. GRANULAR BACKFILL FOR STRUCTURES SHALL BE COMPACTED IN 6" MAX. LIFTS.
2 8. ALL GROUND DEWATERING FLOWS SHALL BE DIRECTED THROUGH A DEWATERING BAG/BASIN PRIOR TO DISCHARGE.



CULVERT LONGITUDINAL SECTION
SCALE: 1" = 10'



RELOCATED EPHEMERAL STREAM TYPICAL SECTION
SCALE: 1" = 4'



CULVERT TYPICAL SECTION
SCALE: 1" = 4'

VHB
Vanasse Hangen Brustlin, Inc.
Transportation
Land Development
Environmental Services
7056 U.S. Route 7, P.O. Box 120
North Ferrisburgh, Vermont 05473
802.497.6100 • FAX 802.425.7799

No.	Revision	Date	Appvd.
2	ANR Comments	2/6/2015	TMG
1	Revised Streambed Stone Fill Notes	2/2/2014	RW

Designed by	Drawn by	Checked by
CAD checked by		Approved by
Scale As Shown	Date December 13, 2013	

Project Title
Halifax Quarry
C.A.Denison Lumber Co., Inc.
Halifax, Vermont

Issued for
Permitting

Not Approved for Construction

Drawing Title
Stream Crossing Plan

Drawing Number
C-3

Sheet 3 of 11

Project Number
57595.00



LEGEND:

- PROPOSED 50FT RIPARIAN BUFFER
- EXISTING CULVERT
- VHB DELINEATED EPHEMERAL STREAM (2012)
- VHB DELINEATED INTERMITTENT STREAM (2012)
- VHB DELINEATED PERENNIAL STREAM (2012)
- VHB DELINEATED CLASS II WETLAND (2012/2013)
- VHB DELINEATED CLASS III WETLAND (2012/2013)
- WETLANDS CONTINUE
- 50' CLASS II WETLAND BUFFER
- EXISTING 2FT MINOR CONTOUR
- EXISTING 10FT MAJOR CONTOUR
- EXISTING GRAVEL DRIVE
- PROPOSED 2FT MINOR CONTOUR
- PROPOSED 10FT MAJOR CONTOUR
- PROPOSED GRAVEL ROAD
- APPROXIMATE LIMITS OF GRADING
- CONCEPTUAL DRAINAGE FLOW
- QUARRY OPERATIONS: STONE AND GRAVEL EXTRACTION AREAS
- EXISTING LOGGING TRAILS
- SILT FENCE LOCATION
- PERMANENT STREAM BUFFER IMPACT
- TEMPORARY STREAM BUFFER IMPACT

TEMPORARY STONE CHECK DAM INSTALLATION
STA. 1+75 TO 8+50 - INSTALL EVERY 7'-6"
STA. 12+00LT TO 14+85LT - INSTALL EVERY 7'-6"
STA. 12+00RT TO 14+85RT - INSTALL EVERY 12'-6"
STA. 14+85LT TO 18+75LT - INSTALL EVERY 5'-0"
STA. 14+85RT TO 18+75RT - INSTALL EVERY 8'-4"
STA. 18+75LT TO 22+60LT - INSTALL EVERY 7'-6"
STA. 18+75RT TO 22+60RT - INSTALL EVERY 12'-6"

NOTES:
1. INSTALL CHECK DAMS EVERY 50' FOR STATIONS NOT LISTED ABOVE
2. CONTRACTOR TO REMOVE ALL STONE CHECK DAMS UPON SITE STABILIZATION

VHB
Vanasse Hangen Brustlin, Inc.
Transportation
Land Development
Environmental Services
7056 U.S. Route 7, P.O. Box 120
North Ferrisburgh, Vermont 05473
802.497.6100 • FAX 802.425.7799

N

80 0 80 160
SCALE IN FEET

No.	Revision	Date	Appvd.
3	ANR Comments	2/6/2015	TMC
2	ANR Comments	12/19/2014	TMC
1	Revision per DEC Comments	1/27/2014	TMM

Designed by | Drawn by | Checked by
CAD checked by | Approved by
Scale 1" = 80' | Date December 13, 2013

Project Title
Halifax Quarry
C.A.Denison Lumber Co., Inc.
Halifax, Vermont

Issued for
Permitting

Not Approved for Construction

Drawing Title
Overall Drainage Plan
ESPC PLAN

Drawing Number
C-4

Sheet of
4 11

Project Number
57595.00

57595.00_GD.DWG



VHB

Vanasse Hangen Brustlin, Inc.

Transportation
Land Development
Environmental Services

7056 U.S. Route 7, P.O. Box 120
North Ferrisburgh, Vermont 05473
802.497.6100 • FAX 802.425.7799

N

20 0 20 40
SCALE IN FEET

No.	Revision	Date	Appvd.
2	ANR Comments	2/6/2015	TMG
1	ANR Comments	12/19/2014	TMG

Designed by | Drawn by | Checked by

CAD checked by | Approved by

Scale 1"=20' | Date December 13, 2013

Project Title

Halifax Quarry
C.A.Denison Lumber Co., Inc.

Halifax, Vermont

Issued for

Permitting

Not Approved for Construction

Drawing Title

Stormwater Treatment Pond 1 Plan

Drawing Number

C-5

Sheet 5 of 11

Project Number
57595.00



VHB
Vanasse Hangen Brustlin, Inc.
Transportation
Land Development
Environmental Services
7056 U.S. Route 7, P.O. Box 120
North Ferrisburgh, Vermont 05473
802.497.6100 • FAX 802.425.7799

N

20 0 20 40
SCALE IN FEET

No.	Revision	Date	Appvd.

Designed by	Drawn by	Checked by
CAD checked by	Approved by	
Scale 1" = 20'	Date December 13, 2013	

Project Title

Halifax Quarry C.A.Denison Lumber Co., Inc.

Halifax, Vermont

Issued for

Permitting

Not Approved for Construction

Drawing Title

Stormwater Treatment Pond 2 Plan

Drawing Number

C-6

Sheet 6 of 11

Project Number 57595.00



S A A:

NOTES:

1. STONE EXTRACTION TO BE DONE BY EXCAVATION VIA DRILLED AND NATURAL SEAMS/CRACKS IN STONE FACE. STONE WILL BE EXTRACTED IN LIFTS AS MUCH AS POSSIBLE, AS ROCK SEAMS ALLOW.
2. SECTION SHOWN IS GENERALLY INDICATIVE OF EXTRACTION DEPTHS WITHIN EXTRACTION ZONE LIMITS.
3. PROPOSED ACCESS ROAD SUBJECT TO CHANGE AS EXTRACTION PROGRESSES AND LANDSCAPE CHANGES.

Vanasse Hangen Brustlin, Inc.

Transportation
Land Development
Environmental Services

7056 U.S. Route 7, P.O. Box 120
North Ferrisburgh, Vermont 05473
802.497.6100 • FAX 802.425.7799

HORIZONTAL
50 0 50 100
50 0 50 100
VERTICAL
SCALE IN FEET

No.	Revision	Date	Appvd.

Designed by | Drawn by | Checked by

CAD checked by | Approved by

Scale 1" = 50' | Date December 13, 2013

Project Title

Halifax Quarry
C.A.Denison Lumber Co., Inc.

Halifax, Vermont

Issued for

Permitting

Not Approved for Construction

Drawing Title

Site Section A-A'
Extraction Limits

Drawing Number

C-7

Sheet 7 of 11

Project Number
57595.00



NOTE – REFER TO THE RIPRAP CHANNEL DETAIL FOR MATERIAL SPECIFICATIONS

TYPICAL SECTION □OR S□ ALE TO STP□1

11/13

SCALE□1" □4□0"

Source: VHB



NOTE – REFER TO THE RIPRAP CHANNEL DETAIL FOR MATERIAL SPECIFICATIONS

TYPICAL SECTION □OR DIVERSION S□ ALE

11/13

SCALE□1" □4□0"

Source: VHB



ROAD□ AY TYPICAL SECTION STA□11□00 TO □□□□



ROAD□ AY TYPICAL SECTION STA11□00 TO 1□□00



ROAD□ AY TYPICAL SECTION STA□0□00 TO 0□□00

ROAD□ AY TYPICAL SECTIONS

11/13

SCALE□1" □4□0"

Source: VHB

RIPRAP STONE SIZING	
LOCATION	STONE DIA. (D50)
ROADWAY STA. 0+00 TO 09+00 RT	0.8
ROADWAY STA. 0+00 TO 09+00 LT	0.8
ROADWAY STA. 11+00 TO 17+00 RT	1.1
ROADWAY STA. 11+00 TO 17+00 LT	1.4
ROADWAY STA. 17+00 TO 25+63 RT	0.8
ROADWAY STA. 17+00 TO 25+63 LT	1
SWALE TO STP - 1	1.8
SEE TYPICAL SECTIONS FOR CHANNEL DIMENSIONS	



R□r□□ C□□□□□

6/08

N.T.S.

Source: VHB

LD_170

Vanasse Hangen Brustlin, Inc.

Transportation
Land Development
Environmental Services

7056 U.S. Route 7, P.O. Box 120
North Ferrisburgh, Vermont 05473
802.497.6100 • FAX 802.425.7799

No.	Revision	Date	Appvd.

Designed by | Drawn by | Checked by

CAD checked by | Approved by

Scale AS SHO□N | Date December 13, 2013

Project Title

Halifax Quarry
C.A.Denison Lumber Co., Inc.

Halifax, Vermont

Issued for

Permitting

Not Approved for Construction

Drawing Title

Details

Drawing Number

C-8

Sheet 8 of 11

Project Number

57595.00



Notes:

1. LOW PERMEABILITY CORE MATERIAL IS CONTINUOUS FOR THE FULL LENGTH OF THE EMBANKMENT.
2. WHERE PIPES PENETRATE THE LOW PERMEABILITY CORE, PIPE SHALL BE BEDDED IN THE LOW PERMEABILITY CORE MATERIAL.

D[illegible] [illegible] [illegible] S[illegible] 10/08

N.T.S. Source: VHB LD_160



Plan View



Section B-B



Section A-A

O[illegible]r[illegible] S[illegible]S[illegible] 6/08

N.T.S. Source: VHB LD_161



Plan View



Section B-B



Section A-A

S[illegible] [illegible] [illegible] O[illegible] 11/13

N.T.S. Source: VHB LD_161A

FES NO.	X	Y	Z	STONE DIA. (D_{50})
1	10'	12'	1'	6"
2	11'	12'	1'	6"



Plan



Section A-A

[illegible]r[illegible]d E[illegible]d S[illegible] [illegible]ES[illegible] [illegible]S[illegible] Pr[illegible] 5/12

N.T.S. Source: VHB LD_134



ORIFICE ELEVATION										
			LEVEL 1			LEVEL 2			LEVEL 3	
OUTLET STRUCTURE	RIM ELEVATION	18" OUTLET INVERT	QTY.	ORIFICE DIA.	INVERT ELEV.	QTY.	ORIFICE DIA.	INVERT ELEV.	QTY.	OPENING DIM.	INVERT ELEV.
OCS-1	1241.5	1238	1	2"	1238.7	1	4"	1241	1	18"x18"	1241.5

NOTES:

1. PROVIDE "V" KNOCKOUTS FOR PIPES WITH 2" MAX. CLEARANCE TO OUTSIDE OF PIPE. MORTAR ALL PIPE CONNECTIONS.

Section A-A

O[illegible]C[illegible]r[illegible]S[illegible]r[illegible]r: OCS [illegible]

N.T.S. Source: VHB REV



ORIFICE ELEVATION										
			LEVEL 1			LEVEL 2			LEVEL 3	
OUTLET STRUCTURE	RIM INVERT	18" OUTLET INVERT	QTY.	ORIFICE DIA.	INVERT ELEV.	QTY.	ORIFICE DIA.	INVERT ELEV.	QTY.	OPENING DIA.	INVERT ELEV.
OCS-2	1186.0	1182.0	SEE NOTES & INVERT BELOW			1	4"	1184.4	1	18"x18"	1186.0

NOTES:

1. PROVIDE "V" KNOCKOUTS FOR PIPES WITH 2" MAX. CLEARANCE TO OUTSIDE OF PIPE. MORTAR ALL PIPE CONNECTIONS.

Section A-A

O[illegible]C[illegible]r[illegible]S[illegible]r[illegible]r: OCS [illegible]

N.T.S. Source: VHB REV

VHB
Vanasse Hangen Brustlin, Inc.
Transportation
Land Development
Environmental Services
7056 U.S. Route 7, P.O. Box 120
North Ferrisburgh, Vermont 05473
802.497.6100 • FAX 802.425.7799

No.	Revision	Date	Appvd.

Designed by | Drawn by | Checked by

CAD checked by | Approved by

Scale | Date December 13, 2013

Project Title

Halifax Quarry C.A.Denison Lumber Co., Inc.

Halifax, Vermont

Issued for

Permitting

Not Approved for Construction

Drawing Title

Details

Drawing Number

C-9

Sheet of 9 11

Project Number 57595.00

57595_DT.DWG





Section A-A



SECTION 'A-A' **SECTION 'B-B'**

Notes:

1. STONE WILL BE PLACED ON A FILTER FABRIC FOUNDATION TO THE LINES, GRADES AND LOCATIONS SHOWN IN THE PLAN USING A WELL GRADED STONE MATRIX 2 TO 9 INCHES IN SIZE.
2. SET SPACING OF CHECK DAMS TO ASSURE THAT THE ELEVATIONS OF THE CREST OF THE DOWNSTREAM DAM IS AT THE SAME ELEVATION OF THE TOE OF THE UPSTREAM DAM.
3. EXTEND THE STONE A MINIMUM OF 1.5 FEET BEYOND THE DITCH BANKS TO PREVENT CUTTING AROUND THE DAM.
4. PROTECT THE CHANNEL DOWNSTREAM OF THE LOWEST CHECK DAM FROM SCOUR AND EROSION WITH STONE OR LINER AS APPROPRIATE.
5. ENSURE THAT CHANNEL APPURTENANCES SUCH AS CULVERT ENTRANCES BELOW CHECK DAMS ARE NOT SUBJECT TO DAMAGE OR BLOCKAGE FROM DISPLACED STONE.
6. MAXIMUM DRAINAGE AREA ABOVE CHECK DAM SHALL NOT EXCEED 2 AC.



EMBANKMENT SECTION THRU RISER

CONSTRUCTION SPECIFICATIONS

1. NOTE: THIS PRACTICE IS NOT CALLED OUT AS NEEDED ON THE PLANS, YET IS OFFERED FOR CONSIDERATION DURING CONSTRUCTION IF ADDITIONAL MEASURES BEYOND THOSE DEPICTED ARE REQUIRED.
2. AREA UNDER EMBANKMENT SHALL BE CLEARED, GRUBBED AND STRIPPED OF ANY VEGETATION AND ROOT MAT. THE POOL AREA SHALL BE CLEARED.
3. THE FILL MATERIAL FOR THE EMBANKMENT SHALL BE FREE OF ROOTS OR OTHER WOODY VEGETATION AS WELL AS OVER-SIZED STONES, ROCKS, ORGANIC MATERIAL, OR OTHER OBJECTIONABLE MATERIAL. THE EMBANKMENT SHALL BE COMPACTED BY TRAVERSING WITH EQUIPMENT WHILE IT IS BEING CONSTRUCTED.
4. VOLUME OF SEDIMENT STORAGE SHALL BE 3600 CUBIC FEET PER ACRE OF CONTRIBUTORY DRAINAGE.
5. SEDIMENT SHALL BE REMOVED AND TRAP RESTORED TO ITS ORIGINAL DIMENSIONS WHEN THE SEDIMENT HAS ACCUMULATED TO 1/2 THE DESIGN DEPTH OF THE TRAP. REMOVED SEDIMENT SHALL BE DEPOSITED IN A SUITABLE AREA AND STABILIZED.
6. THE STRUCTURE SHALL BE INSPECTED AFTER EACH RAIN AND REPAIRS MADE AS NEEDED.
7. CONSTRUCTION OPERATIONS SHALL BE CARRIED OUT IN SUCH A MANNER THAT EROSION AND SEDIMENT ARE CONTROLLED.
8. THE STRUCTURE SHALL BE REMOVED AND AREA STABILIZED WHEN THE DRAINAGE AREA HAS BEEN PROPERLY STABILIZED.
9. ALL FILL SLOPES SHALL BE 2:1 OR FLATTER; CUT SLOPES 1:1 OR FLATTER.
10. ALL PIPE CONNECTIONS SHALL BE WATERTIGHT.
11. THE TOP 2/3 OF THE RISER SHALL BE PERFORATED WITH ONE (1) INCH DIAMETER HOLES OR SLITS SPACED SIX (6) INCHES VERTICALLY AND HORIZONTALLY AND PLACED IN THE CONCAVE PORTION OF PIPE. NO HOLES WILL BE ALLOWED WITHIN SIX (6) INCHES OF THE HORIZONTAL BARREL.
12. THE RISER SHALL BE WRAPPED WITH 1/4 TO 1/2 INCH HARDWARE CLOTH WIRE THEN WRAPPED WITH FILTER CLOTH (HAVING AN EQUIVALENT SIEVE SIZE OF 40-80). THE FILTER CLOTH SHALL EXTEND SIX (6) INCHES ABOVE THE HIGHEST HOLE AND SIX (6) INCHES BELOW THE LOWEST HOLE. WHERE ENDS OF THE FILTER CLOTH COME TOGETHER, THEY SHALL BE OVER-LAPPED, FOLDED AND STAPLED TO PREVENT BYPASS.
13. STRAPS OR CONNECTING BANDS SHALL BE USED TO HOLD THE FILTER CLOTH AND WIRE FABRIC IN PLACE. THEY SHALL BE PLACED AT THE TOP AND BOTTOM OF THE CLOTH.
14. FILL MATERIAL AROUND THE PIPE SPILLWAY SHALL BE HAND COMPACTED IN FOUR (4) INCH LAYERS. A MINIMUM OF TWO (2) FEET OF HAND COMPACTED BACKFILL SHALL BE PLACED OVER THE PIPE SPILLWAY BEFORE CROSSING IT WITH CONSTRUCTION EQUIPMENT.
15. THE RISER SHALL BE ANCHORED WITH EITHER A CONCRETE BASE OR STEEL PLATE BASE TO PREVENT FLOTATION. FOR CONCRETE BASED THE DEPTH SHALL BE TWELVE (12) INCHES WITH THE RISER EMBEDDED NINE (9) INCHES. A 1/4 INCH MINIMUM THICKNESS STEEL PLATE SHALL BE ATTACHED TO THE RISER BY A CONTINUOUS WELD AROUND THE BOTTOM TO FORM A WATERTIGHT CONNECTION AND THEN PLACE TWO (2) FEET OF STONE, GRAVEL, OR TAMPED EARTH ON THE PLATE.

L□□□S□r□□d□r D□□□□

6/08

N.T.S. Source: VHB LD_172

S□□□□C□□□□D□□

12/12

N.T.S. Source: VHB / VT S+S EPSC LD_

P□□□O□□□□S□d□□ □□□Tr□□

12/12

N.T.S. Source: VHB / VT S+S EPSC LD_



CONSTRUCTION SPECIFICATIONS

1. NOTE: THIS PRACTICE IS NOT CALLED OUT AS NEEDED ON THE PLANS, YET IS OFFERED FOR CONSIDERATION DURING CONSTRUCTION IF ADDITIONAL MEASURES BEYOND THOSE DEPICTED ARE REQUIRED.
2. AREA UNDER EMBANKMENT SHALL BE CLEARED, GRUBBED AND STRIPPED OF ANY VEGETATION AND ROOT MAT. THE POOL AREA SHALL BE CLEARED.
3. THE FILL MATERIAL FOR THE EMBANKMENT SHALL BE FREE OF ROOTS AND OTHER WOODY VEGETATION AS WELL AS OVER-SIZED STONES, ROCKS, ORGANIC MATERIAL OR OTHER OBJECTIONABLE MATERIAL. THE EMBANKMENT SHALL BE COMPACTED BY TRAVERSING WITH EQUIPMENT WHILE IT IS BEING CONSTRUCTED.
4. ALL CUT AND FILL SLOPES SHALL BE 2:1 OR FLATTER.
5. THE STONE USED IN THE OUTLET SHALL BE SMALL RIPRAP 4"-8" ALONG WITH A 1' THICKNESS OF 2" AGGREGATE PLACED ON THE UP-GRADE SIDE ON THE SMALL RIPRAP OR EMBEDDED FILTER CLOTH IN THE RIPRAP.
6. SEDIMENT SHALL BE REMOVED AND TRAP RESTORED TO ITS ORIGINAL DIMENSIONS WHEN THE SEDIMENT HAS ACCUMULATED TO 1/2 THE DESIGN DEPTH OF THE TRAP.
7. THE STRUCTURE SHALL BE INSPECTED AFTER EACH RAIN AND AS REQUIRED BY THE PERMIT.
8. CONSTRUCTION OPERATIONS SHALL BE CARRIED OUT IN SUCH A MANNER THAT EROSION AND WATER POLLUTION IS MINIMIZED.
9. THE STRUCTURE SHALL BE REMOVED AND THE AREA STABILIZED WHEN THE DRAINAGE AREA HAS BEEN PROPERLY STABILIZED.
10. MAXIMUM DRAINAGE AREA: 5 ACRES

S□□□□O□□□□S□d□□ □□□Tr□□

12/12

N.T.S. Source: VHB / VT S+S EPSC LD_



Plan View



Cross-Section

Notes:

1. NUMBER OF BALES MAY VARY DEPENDING ON SITE CONDITIONS.
2. THE BASIN TO BE SIZED TO PREVENT DISCHARGE WATER FROM OVERTOPPING BASIN.

D□□ □□r□□S□r□□ □□□□□□□

2/11

N.T.S. Source: VHB LD_690

MULCH MATERIAL AND APPLICATION

MULCH MATERIAL	QUALITY STANDARDS	PER 1,000 SQ-FT	PER ACRE	DEPTH OF APPLICATION
WOOD CHIPS OR SHAVINGS	AIR DRIED, FREE OF OBJECTIONABLE MATERIAL	500 - 900 LBS	10 - 20 TONS	2" - 7"
WOOD FIBER CELLULOSE (PARTIALLY DIGESTED WOOD FIBERS)	MADE FROM NATURAL WOOD USUALLY WITH GREEN DYE AND DISPERSING AGENT	50 LBS	2,000 LBS	N/A
GRAVEL, CRUSHED STONE OR SLAG	WASHED; SIZE 2B OR 3A - 1 1/2"	9 CY	405 CY	3"
HAY OR STRAW	AIR-DRIED; FREE OF UNDESIRABLE SEEDS AND COARSE MATERIALS	90 - 100 LBS, 2-3 BALES	2 TONS (100-120 BALES)	COVER ABOUT 90% SURFACE
COMPOST	UP TO 3" PIECES, MODERATELY TO HIGHLY STABLE	3 - 9 CY	3 - 9 CY	1-3"
Erosion Control Mix	WELL-GRADED MIXTURE OF PARTICLE SIZES. ORGANIC CONTENT BETWEEN 80-100% DRY WEIGHT. PARTICLE SIZE SHALL PASS 6" SCREEN (100%)	*Slopes 3(Hz.):1(Vert.) = 2 inch depth plus additional 1/2 inch depth per 20 ft. of slope up to 100 ft. **Slopes between 3(Hz.):1(Vert.) and 2(Hz.):1(Vert.) = 4 inch depth plus additional 1/2 inch per 20 ft. of slope up to 100 ft. ***Slopes steeper than 2(Hz.):1(Vert.) applicability to specific site and mulch depth to be reviewed and approved prior to use by OPSC or EPSC Specialist		

Notes:

1. APPLY TACKIFIER AS NEEDED TO MINIMIZE POTENTIAL FOR MULCH TO BLOW AWAY.
2. MULCH MUST NOT CONTAIN INVASIVE PLANT SPECIES. (SEEDS OR SEEDLINGS)
3. TACKIFIER MAY BE WATER, NETTING, OR SIMILAR.
4. OTHER THAN EROSION CONTROL MIX, MULCH IS NOT TO BE INSTALLED ON SLOPES > 3:1.

M□□□ T□□□

12/12

N.T.S. Source: VHB LD_

TEMPORARY SEEDING MIX		
TYPE	SEASON	RATE (LBS/ACRE)
RYEGRASS (ANNUAL OR PERENNIAL)	APRIL 15 - SEPTEMBER 15	20
"AROOSTOOK" WINTER RYE	SEPTEMBER 15 - APRIL 15	90

PERMANENT SEEDING MIX*		
TYPE	SEASON	RATE (LBS/ACRE)
BIRDSFOOT TREFOIL(1)**	APRIL 15 - SEPTEMBER 15	5
COMMON WHITE CLOVER (1)**	APRIL 15 - SEPTEMBER 15	8
TALL FESCUE (2)	APRIL 15 - SEPTEMBER 15	10
REDTOP (3)	APRIL 15 - SEPTEMBER 15	2
RYEGRASS (PERENNIAL) (3)	APRIL 15 - SEPTEMBER 15	5

*PERMANENT SEEDING MIX IS A COMBINATION OF BIRDSFOOT TREFOIL OR COMMON WHITE CLOVER PLUS TALL FESCUE PLUS REDTOP OR RYEGRASS (PERENNIAL). I.E. PERMANENT SEEDING MIX = (1) + (2) + (3). (SEE PAGE 4.27 OF THE VERMONT STANDARDS AND SPECIFICATIONS FOR EROSION PREVENTION AND SEDIMENT CONTROL.)
** ADD INOCULANT IMMEDIATELY PRIOR TO SEEDING

RIPARIAN AND WETLAND SEEDING MIX		
TYPE	SEASON	RATE (LBS/ACRE)
"WET MEADOW AND DETENTION BASIN"* OR APPROVED EQUAL	APRIL 15 -SEPTEMBER 15	35

*SEED SPECIFIED IS FROM VERMONT WETLAND PLANT SUPPLY AND COMPOSED OF THE FOLLOWING SPECIES: PANICUM VIRGATUM, ELYMUS VIRGINICUS, FESTUCA RUBRA, CAREX VULPINOIDEA, CAREX SCOPARIA, SCIRPUS CYPERINUS, SCIRPUS ATROVIRENS, BIDENS CERNUA, EUPATORIUM PERFOLIATUM, EUPATORIADELPHUS MACULATUS, JUNCUS EFFUSUS, ONOCLEA SENSIBILIS, VERBENA HASTATA, SYMPHYOTRICHUM NOVAE-ANGLIAEA

UPLAND NATURAL COMMUNITY MIX		
TYPE	SEASON	RATE (LBS/ACRE)
"VERMONT CONSERVATION AND WILDLIFE"* OR APPROVED EQUIVALENT	APRIL 15 -SEPTEMBER 15	25

*SEED SPECIFIED IS, IN PART, FROM VERMONT WETLAND PLANT SUPPLY AND COMPOSED OF THE FOLLOWING SPECIES: ELYMUS VIRGINICUS, FESTUCA RUBRA, SCHIZACHYRIUM SCOPARIUM, ANDROPOGON GERARDII, PANICUM CLANDESTINUM, SORGHASTRUM NUTANS, ASCLEPIA SYRIACA, VERBENA HASTATA, EUPATORIUM FISTULOSUM, EUTHAMIA GRAMINIFOLIA, SOLIDAGO JUNCEA, SYMPHYOTRICHUM NOVAE-ANGLIAE
NOTE: SEE MIX SHOULD EXCLUDE BOTH CHAMAECRISTA FASCICULATA AND HELIOPSIS HELIANTHOIDES, WHICH ARE BOTH COMMONLY INCLUDED IN THIS COMMERCIAL MIX.

S□d□□S□□□□□□□□□□

06/13

N.T.S. Source: VHB LD_

VHB
Vanasse Hangen Brustlin, Inc.
Transportation
Land Development
Environmental Services
7056 U.S. Route 7, P.O. Box 120
North Ferrisburgh, Vermont 05473
802.497.6100 • FAX 802.425.7799

No.	Revision	Date	Appvd.
1	Revision per DEC comments	1/27/14	TJM

Designed by | Drawn by | Checked by
CAD checked by | Approved by
Scale | Date December 13, 2013

Project Title
Halifax Quarry
C.A.Denison Lumber
Co., Inc.

Halifax, Vermont

Issued for
Permitting

Not Approved for Construction

Drawing Title
Details

Drawing Number
C-10

Sheet of
10 11

Project Number
57595.00



Notes:

1. STONE SIZE: USE 1 TO 4 INCH DIAMETER STONE, OR RECLAIMED OR RECYCLED CONCRETE EQUIVALENT.
2. LENGTH: NOT LESS THAN 50 FEET.
3. THICKNESS: NOT LESS THAT 8 INCHES.
4. WIDTH: EXIT WIDTH SHALL BE A TWELVE (12) FOOT MINIMUM, BUT NOT LESS THAN THE FULL WIDTH AT POINTS WHERE INGRESS OR EGRESS OCCURS.
5. GEOTEXTILE: MUST BE PLACED OVER THE ENTIRE AREA PRIOR TO PLACING STONE.
6. SURFACE WATER: ALL SURFACE WATER FLOWING OR DIVERTED TOWARD CONSTRUCTION EXITS SHALL BE PIPED BENEATH THE EXIT. IF PIPING IS IMPRACTICAL, A MOUNTABLE BERM WITH 5:1 SLOPES WILL BE PERMITTED.
7. MAINTENANCE: THE EXIT SHALL BE MAINTAINED IN A CONDITION WHICH WILL PREVENT TRACKING OR FLOWING OF SEDIMENT ONTO PUBLIC RIGHTS-OF-WAY, ALL SEDIMENT SPILLED, DROPPED, WASHED OR TRACKED ONTO PUBLIC RIGHTS-OF-WAY MUST BE REMOVED IMMEDIATELY.
8. WHEN WASHING IS REQUIRED IT SHALL BE DONE ON AN AREA STABILIZED WITH STONE AND WHICH DRAINS INTO AN APPROVED SEDIMENT TRAPPING DEVICE.
9. PERIODIC INSPECTION AND NEEDED MAINTENANCE SHALL BE PROVIDED ACCORDING TO PERMIT REQUIREMENTS.
10. STABILIZED CONSTRUCTION EXIT SHALL BE REMOVED PRIOR TO FINAL FINISH MATERIALS BEING INSTALLED.

Stabilized Construction Entrance/Exit

2/09

N.T.S. Source: VHB LD_682-VT



Notes:

1. SEE DETAIL # 2 ON SHEET ANGP-T-G-012 FOR LIST OF APPROPRIATE PERIMETER CONTROLS TO USE.
2. FILTER CLOTH SHALL BE EITHER FILTER X, MIRAFI 100X, STABILINKA T140N OR APPROVED EQUIVALENT.
3. FOR FILTER CLOTH FENCE WHEN ELONGATION IS >50%, POST SPACING SHALL NOT EXCEED 4 FT. FOR FILTER CLOTH FENCE WHEN ELONGATION IS <50%, POST SPACING SHALL NOT EXCEED 6 FT.
4. WHEN TWO SECTIONS OF FILTER CLOTH ADJOIN EACH OTHER THEY SHALL BE OVER-LAPPED BY 6 INCHES AND FOLDED.
5. PREFABRICATED UNITS SHALL BE GEOFAB, ENVIROFENCE OR APPROVED EQUIVALENT.
6. MAINTENANCE SHALL BE PERFORMED AS NEEDED AND MATERIAL REMOVED WHEN SEDIMENT REACHES HALF OF FABRIC HEIGHT AND DISPOSED OF IN AN UPLAND AREA.
7. PERIMETER CONTROLS SHALL NOT CROSS ACTIVE ACCESS ROUTES (E.G., ROADS) IR ACTIVE FLOW PATHS (E.G., LARGER STREAMS/RIVERS).
8. PERIMETER CONTROLS SHALL REMAIN IN PLACE AND BE MAINTAINED/REPLACED AS NEEDED UNTIL FINAL STABILIZATION IN THE AREA HAS BEEN ACHIEVED.

S□□□□□□□

12/12

N.T.S. Source: VHB LD_650VT



Notes:

1. SEE DETAIL #2 ON SHEET ANGP-T-G-012 FOR LIST OF APPROPRIATE PERIMETER CONTROLS TO USE
2. FILTER CLOTH SHALL BE EITHER FILTER X, MIRAFI 100X, STABILINKA T140N OR APPROVED EQUIVALENT.
3. FOR FILTER CLOTH FENCE WHEN ELONGATION IS >50%, POST SPACING SHALL NOT EXCEED 4 FT. FOR FILTER CLOTH FENCE WHEN ELONGATION IS <50%, POST SPACING SHALL NOT EXCEED 6 FT.
4. WHEN TWO SECTIONS OF FILTER CLOTH ADJOIN EACH OTHER THEY SHALL BE OVER-LAPPED BY 6 INCHES AND FOLDED.
5. PREFABRICATED UNITS SHALL BE GEOFAB, ENVIROFENCE OR APPROVED EQUIVALENT.
6. MAINTENANCE SHALL BE PERFORMED AS NEEDED AND MATERIAL REMOVED WHEN SEDIMENT REACHES HALF OF FABRIC HEIGHT AND DISPOSED OF IN AN UPLAND AREA.
7. PERIMETER CONTROLS SHALL NOT CROSS ACTIVE ACCESS ROUTES (E.G., ROADS) OR ACTIVE FLOW PATHS (E.G., LARGER STREAMS/RIVERS).
8. PERIMETER CONTROLS SHALL REMAIN IN PLACE AND BE MAINTAINED/REPLACED AS NEEDED UNTIL FINAL STABILIZATION IN THE AREA HAS BEEN ACHIEVED.

R□□□r□d S□□□□□□□ □□□ □ r□M□□

12/12

N.T.S. Source: VHB LD_651



Notes:

1. BEGIN AT THE TOP OF BLANKET INSTALLATION AREA BY ANCHORING BLANKET IN A 6" DEEP TRENCH BACKFILL AND COMPACT TRENCH AFTER STAPLING.
2. ROLL THE BLANKET DOWN THE SLOPE IN THE DIRECTION OF THE WATER FLOW.
3. THE EDGES OF BLANKETS MUST BE STAPLED WITH APPROX. 4 INCH OVERLAP WHERE 2 OR MORE STRIP WIDTHS ARE REQUIRED.
4. WHEN SPLICING BLANKETS, PLACE UPPER BLANKET END OVER LOWER END WITH 6 INCH (MIN.) OVERLAP AND STAPLE BOTH TOGETHER.
5. METHOD OF INSTALLATION SHALL BE AS PER MANUFACTURER'S RECOMMENDATIONS.
6. EROSION CONTROL BLANKETS SHALL BE USED IN ALL AREAS WHERE SLOPES EXCEED 3:1.

Er□□□□ C□□r□□□□□□□S□□□I□□□□□□□□□

1/10

N.T.S. Source: VHB REV LD_68C



Notes:

1. BARRIER MESH TAPE OR ROPE SHALL BE INSTALLED ALONG THE PERIMETER OF THE PROJECT AREA TO DEMARCATE THE LIMIT OF DISTURBANCE. NO EARTHWORK OR STORAGE OF MATERIALS SHALL BE CONDUCTED BEYOND THIS LIMIT WITHOUT PRIOR APPROVAL FROM THE OSPC.
2. USE 3" ORANGE BARRIER MESH TAPE OR 1/2" YELLOW POLYPROPYLENE ROPE.
3. WITHIN 50' OF WATER RESOURCE AREAS, USE 2-3 ROWS OF TAPE OR ROPE. BEYOND 50' OF WATER RESOURCE AREAS USE 1 ROW OF TAPE OR ROPE.
4. TAPE OR ROPE MAY BE FASTENED TO STAKES, TREES, OR OTHER APPROPRIATE FIXED OBJECTS.
5. PROJECT DEMARCATION SHALL NOT CROSS ACTIVE ACCESS ROUTES (E.G. ROADS). PROJECT DEMARCATION MAY CROSS RESOURCES AREAS WITH EXCEPTION OF LARGER WATER BODIES WHERE IT IS NOT FEASIBLE OR ADVISABLE.
6. PROJECT DEMARCATION SHALL REMAIN IN PLACE AND BE MAINTAINED/REPLACED AS NEEDED UNTIL FINAL STABILIZATION IN THE AREA HAS BEEN ACHIEVED.

□□rr□r M□□ T□□□□r R□□□

12/12

N.T.S. Source: VHB LD_



Notes:

1. BARRIER FLAGGING OR PAINT SHALL BE INSTALLED ALONG THE PERIMETER OF THE PROJECT AREA TO DEMARCATE THE LIMIT OF DISTURBANCE. NO EARTHWORK OR STORAGE OF MATERIALS SHALL BE CONDUCTED BEYOND THIS LIMIT WITHOUT PRIOR APPROVAL FROM THE OSPC.
2. FLAGGING OR PAINT MAY BE FASTENED TO STAKES, TREES, OR OTHER APPROPRIATE FIXED OBJECTS.
3. PROJECT DEMARCATION SHALL NOT CROSS ACTIVE ACCESS ROUTES (E.G. ROADS). PROJECT DEMARCATION MAY CROSS RESOURCE AREAS WITH THE EXCEPTION OF LARGER WATER BODIES WHERE IT IS NOT FEASIBLE OR ADVISABLE.
4. PROJECT DEMARCATION SHALL REMAIN IN PLACE AND BE MAINTAINED/REPLACED AS NEEDED UNTIL FINAL STABILIZATION IN THE AREA HAS BEEN ACHIEVED.

□□rr□r □□□□□□□ □r P□□□

12/12

N.T.S. Source: VHB LD_



Notes:

1. CONSTRUCTION/SNOW FENCE SHALL BE INSTALLED WITHIN 50' OF A WATER RESOURCE, (STREAM, BROOK, LAKE, POND, ETC.) UNLESS THE AREA IS DENSELY WOODED, IN WHICH CASE 2 TO 3 ROWS OF ORANGE BARRIER MESH TAPE OR ROPE MAY BE USED.
2. CONSTRUCTION/SNOW FENCE SHALL NOT CROSS ACTIVE ACCESS ROUTES (E.G. ROADS). CONSTRUCTION/SNOW FENCE MAY CROSS RESOURCE AREAS WITH THE EXCEPTION OF LARGER WATER BODIES WHERE IT IS NOT FEASIBLE OR ADVISABLE.
3. CONSTRUCTION/SNOW FENCE SHALL REMAIN IN PLACE AND BE MAINTAINED/REPLACED AS NEEDED UNTIL FINAL STABILIZATION IN THE AREA HAS BEEN ACHIEVED.

C□□□r□□□□□□S□□□ □□□□

12/12

N.T.S. Source: VHB LD_651



Notes:

1. ENTRANCE WIDTH SHALL BE A TWENTY-FIVE (25) FOOT MINIMUM, BUT NOT LESS THAN THE FULL WIDTH AT POINTS WHERE INGRESS OR EGRESS OCCURS.
2. THE ENTRANCE SHALL BE MAINTAINED IN A CONDITION WHICH SHALL PREVENT TRACKING OR FLOWING OF SEDIMENT AWAY FROM WORK SITE. THIS MAY REQUIRE PERIODIC TOP DRESSING WITH ADDITIONAL STONE AS CONDITIONS DEMAND AND REPAIR OR CLEANOUT OF ANY MEASURES USED TO TRAP SEDIMENT. ALL SEDIMENT SPILLED, DROPPED, WASHED OR TRACKED ONTO PUBLIC RIGHTS-OF-WAY MUST BE REMOVED IMMEDIATELY. BERM SHALL BE PERMITTED. PERIODIC INSPECTION AND MAINTENANCE SHALL BE PROVIDED AS NEEDED.
3. STABILIZED CONSTRUCTION EXIT SHALL BE REMOVED PRIOR TO FINAL FINISH MATERIALS BEING INSTALLED.

S□□□□□□□d C□□□r□□□□□□ E□□

6/08

N.T.S. Source: VHB REV LD_682

VHB
Vanasse Hangen Brustlin, Inc.
Transportation
Land Development
Environmental Services
7056 U.S. Route 7, P.O. Box 120
North Ferrisburgh, Vermont 05473
802.497.6100 • FAX 802.425.7799

No.	Revision	Date	Appvd.
1	Revision per DEC comments	1/27/14	TM

Designed by | Drawn by | Checked by
CAD checked by | Approved by
Scale | Date: December 13, 2013

Project Title
Halifax Quarry
C.A.Denison Lumber Co., Inc.

Halifax, Vermont

Issued for
Permitting

Not Approved for Construction

Drawing Title
Details

Drawing Number
C-11

Sheet 11 of 11

Project Number
57595.00



LEGEND:

- PROPOSED 50FT RIPARIAN BUFFER
- EXISTING CULVERT
- VHB DELINEATED EPHEMERAL STREAM (2012)
- VHB DELINEATED INTERMITTENT STREAM (2012)
- VHB DELINEATED PERENNIAL STREAM (2012)
- VHB DELINEATED CLASS II WETLAND (2012/2013)
- VHB DELINEATED CLASS III WETLAND (2012/2013)
- WETLANDS CONTINUE
- 50' CLASS II WETLAND BUFFER
- EXISTING 2FT MINOR CONTOUR
- EXISTING 10FT MAJOR CONTOUR
- EXISTING GRAVEL DRIVE
- PROPOSED 2FT MINOR CONTOUR
- PROPOSED 10FT MAJOR CONTOUR
- PROPOSED GRAVEL ROAD
- APPROXIMATE LIMITS OF GRADING
- CONCEPTUAL DRAINAGE FLOW
- QUARRY OPERATIONS: STONE AND GRAVEL EXTRACTION AREAS
- EXISTING LOGGING TRAILS

N

80 0 80 160
SCALE IN FEET

PERMANENT SEEDING MIX*		
TYPE	SEASON	RATE (LBS/ACRE)
BIRDSFOOT TREFOIL(1)**	APRIL 15 – SEPTEMBER 15	5
COMMON WHITE CLOVER (1)**	APRIL 15 – SEPTEMBER 15	8
TALL FESCUE (2)	APRIL 15 – SEPTEMBER 15	10
REDTOP (3)	APRIL 15 – SEPTEMBER 15	2
RYEGRASS (PERENNIAL) (3)	APRIL 15 – SEPTEMBER 15	5
*PERMANENT SEEDING MIX IS A COMBINATION OF BIRDSFOOT TREFOIL OR COMMON WHITE CLOVER PLUS TALL FESCUE PLUS REDTOP OR RYEGRASS (PERENNIAL). I.E. PERMANENT SEEDING MIX = (1) + (2) + (3). (SEE PAGE 4.27 OF THE VERMONT STANDARDS AND SPECIFICATIONS FOR EROSION PREVENTION AND SEDIMENT CONTROL.) ** ADD INOCULANT IMMEDIATELY PRIOR TO SEEDING		

UPLAND NATURAL COMMUNITY MIX		
TYPE	SEASON	RATE (LBS/ACRE)
"VERMONT CONSERVATION AND WILDLIFE"* OR APPROVED EQUIVALENT	APRIL 15 –SEPTEMBER 15	25
*SEED SPECIFIED IS, IN PART, FROM VERMONT WETLAND PLANT SUPPLY AND COMPOSED OF THE FOLLOWING SPECIES: ELYMUS VIRGINICUS, FESTUCA RUBRA, SCHIZACHYRIUM SCOPARIUM, ANDROPOGON GERARDII, PANICUM CLANDESTINUM, SORGHASTRUM NUTANS, ASCLEPIA SYRIACA, VERBENA HASTATA, EUPATORIUM FISTULOSUM, EUTHAMIA GRAMINIFOLIA, SOLIDAGO JUNCEA, SYMPHYOTRICHUN NOVAE–ANGLIAE NOTE: SEE MIX SHOULD EXCLUDE BOTH CHAMAECRISTA FASCICULATA AND HELIOPSIS HELIANTHOIDES, WHICH ARE BOTH COMMONLY INCLUDED IN THIS COMMERCIAL MIX.		

S□d□□S□□□□□□□□□□□ 06/13

N.T.S. Source: VHB LD_

NOTES:

1. ALL EQUIPMENT, REFUSE, AND ARTIFICIAL MATERIALS WITHIN THE QUARRY SHALL BE REMOVED AND TRANSPORTED OFF SITE TO BE RE–USED OR PROPERLY DISPOSED OF.
2. OVERBURDEN AND TOPSOIL MATERIALS ARE TO BE STORED ON SITE WITHIN THE QUARRY AREA DURING QUARRY OPERATION. ALL TOPSOIL AND OVERBURDEN MATERIAL SHALL BE PLACED/RETURNED TO THE QUARRY BENCHES AND FLOOR AS PART OF THE SITE RECLAMATION AND STABILIZATION. APPLY SEED, MULCH, AND EROSION CONTROLS TO RETAIN SOILS AND PROMOTE THE RETURN OF ADJACENT NATIVE VEGETATION.
3. SEEDING SHALL BE PER THE SEEDING SPECIFICATIONS, THIS SHEET. SEEDING MIX TO BE AN UPLANDS/CONSERVATION MIX, WEED FREE, WITH NO INVASIVES.
4. LARGE STONE BLOCKS TO BE PLACED AROUND THE TOP CREST PERIMETER OF THE QUARRY IN AN OFFSET PATTERN, WITH MAX. 10' SPACING BETWEEN STONES. APPROXIMATELY 15' OUT FROM THE TOP CREST PERIMETER A NEW CHAIN–LINK FENCE IS TO BE INSTALLED (SEE PLAN). STONE BLOCKS ARE TO BE LOCATED BETWEEN FENCE AND QUARRY CREST.
5. IF EXCESS ROCK IS AVAILABLE, ROCK PILES (5' HIGH X 10' X 10') MAY BE LEFT ON BENCHES IN DISCREET AREAS TO PROMOTE BOBCAT HABITAT. PLACE ROCKS IN A MANNER THAT CREATES VOIDS/CAVITIES IN THE PILE FOR POTENTIAL DEN SITES.
6. FOR CULVERTS TO BE REMOVED AFTER QUARRY OPERATIONS ARE COMPLETE:
   a. FINAL STREAM WIDTH TO MATCH EXISTING STREAM WIDTH
   b. FINAL SIDE SLOPES ADJACENT TO STREAMS ARE TO BE NO STEEPER THAN 3h:1v
   c. STREAMBED MATERIAL IS TO MATCH THE EXISTING STREAM BED (SEE STREAM CROSSING PLAN SHEET C–3 FOR SPECIFICATIONS)
   d. ALL DISTURBED AREAS OUTSIDE OF THE STREAM ARE TO BE STABILIZED (SEEDED AND MULCHED)

VHB
Vanasse Hangen Brustlin, Inc.
Transportation
Land Development
Environmental Services
7056 U.S. Route 7, P.O. Box 120
North Ferrisburgh, Vermont 05473
802.497.6100 • FAX 802.425.7799

No.	Revision	Date	Appvd.
1	ANR comments	12/19/14	TM□

Designed by | Drawn by | Checked by
CAD checked by | Approved by
Scale 1"□80□ | Date October 23, 2014

Project Title
Halifax Quarry
C.A.Denison Lumber Co., Inc.

Halifax, Vermont

Issued for
Permitting

Not Approved for Construction

Drawing Title
Reclamation Plan

Drawing Number
RP-1

Sheet of
1 1

Project Number
57595.00